	LINE TABLE						
LINE	LENGTH	BEARING					
L1	88.49'	S69'27'51"W					
L2	53.19'	N25°01'57"W					
L3	92.26'	N05'08'52"E					
L4	45.65'	N59'38'57"W					
L5	30.04	N65'59'37"W					
L6	102.51	N21'42'39"E					
L7	104.23'	N16'39'00"E					
L8	58.32'	S06°23'56"W					

			CURVE	TABLE		
CURVE	LENGTH	RADIUS	CHORD	TANGENT	DELTA	BEARING
C1	382.44	1323.19	381.11'	192.56'	16'33'36"	N3518'59"E
C2	37.95'	25.00'	34.41'	23.71'	86'58'12"	S70"31'17"W
C3	30.50'	20.00'	27.63	19.10'	87'22'36"	N2248'19"W
C4	62.80	953.48'	62.79'	31.41'	03'46'25"	N2316'24"E
C5	34.49'	20.00'	30.37	23.34'	98'49'04"	N64°35'51"E
C6	48.84	490.00'	48.82'	24.44	05'42'38"	S63'08'18"E
C7	50.83	510.00	50.81	25.44	05'42'38"	N63°08'18"W
C8	38.27	25.00'	34.64'	24.02'	87*42'16"	S22"08'29"E
C9	150.32'	60.00'	113.98'	182.21'	143'32'49"	S84*32'25"W
C10	40.16'	950.00'	<b>4</b> 0.16'	20.08	02*25'20"	N13"58'39"E

UNIVERSITY OF N.C.

1.	WHERE EXISTING TOPOGRAPHY ALLOWS, AN 8' PLANTING STRIP AND 5'
	SIDEWALK WILL BE PLACED AS PER CITY CODE ALONG MALLARD CREEK RD.
	THE WALK MAY MEANDER AND THE WIDTH OF THE PLANTING STRIP MAY VARY
	TO SAVE EXISTING TREES AND ACCOMMODATE THE TOPOGRAPHY. IF EXISTING
	TREES (6" OR LARGER) OR TOPOGRAPHY DO NOT ALLOW THE BACK SIDE OF
	THE SIDEWALS TO BE WITHIN 25 FEET OF THE BACK OF THE EXISTING
	MALLARD CREEK ROAD STREET CURB THEN IT WILL BE REQUESTED DURING THE
	BUILDING PERMIT PROCESS THAT THE SIDEWALK REQUIREMENT BE WAIVED.

2 AS EACH BUILDING IS BUILT, THERE WILL BE SIDEWALK FROM THE BUILDING TO A SIDEWALK ALONG A PUBLIC STREET.

NOTES

- 3. MAXIMUM SQUARE FOOTAGE FOR THIS SITE WILL MEET CHARLOTTE-MECKLENBURG PLANNING COMMISSION ZONING ORDINANCES.
- 4. THE AREA WITHIN THE SETBACK ALONG MALLARD CREEK ROAD WILL BE CONSIDERED A WOODLAND BUFFER AREA, THIS AREA SHALL BE LANDSCAPED AND ALL TREES 6" CALIPER AND LARGER SHOULD BE PRESERVED, EXCEPT WHERE EACH LOTS ACCESS DRIVEWAY WILL BE LOCATED.
- 5. THIS PROPERTY IS TO BE USED FOR GENERAL OR MEDICAL OFFICE USE AND ANY OTHER USE ALLOWED UNDER 0-1 ZONING EXCEPT HOTEL/MOTEL OR RESIDENTIAL UNITS.
- 6. THERE ARE CURRENTLY THREE CURB CUTS ALONG MALLARD CREEK ROAD FOR AREA 2. TWO OF THESE CURB CUTS MAY BE USED OR RELOCATED FOR INGRESS/EGRESS PURPOSES.
- 7. A GREENWAY OPEN SPACE EASEMENT WILL BE GRANTED IN THE FLOOE PLAIN AREA ALONG MALLARD CREEK TO THE UNIVERSITY RESEARCH PARK, INC.
- 8. RESIDENTIAL BUFFER WILL BE EITHER CLASS B OR C


N. T. S. MECKLENBURG COUNTY S.W.I.M. BUFFER PORTIONS OF THIS PROPERTY ARE SUBJECT TO WATER QUALITY BUFFER WIDTHS. AREA 2 IS PARTIALLY LOCATED

PROPOSED AREA TO BE REZONED:

IN THE 100 ft. + 50% FLOODFRINGE BUFFER WIDTH.

DEVELOPMENT MUST CONFORM TO THE CHARLOTTE


FLOODWAY REGULATIONS, CHAPTER 9 OF CITY CODE.





PREPARED BY POWER ENGINEERING COMPANY, INC. ENGINEERS - PLANNERS - SURVEYORS

9731-A SOUTHERN PINE BLVD., CHARLOTTE, NC 28273 PH.(704)525-7275 FAX (704)525-2515



1 inch = 200 ft.

PROPOSED ZONING IS 01-CD

APPROVED BY CITY COUNCIL

PROFESSIONAL OFFICE CENTER (a.k.a. WESTBROOK BUSINESS CENTER)

MALLARD CREEK TOWNSHIP, MECKLENBURG COUNTY, NORTH CAROLINA

DECEMBER 13, 2000

01-036 5-18-01 REVISED APRIL 16, 2001 REVISED MAY 18, 2001