

DEVELOPMENT DATA TABLE:

• PETITIONER AND OWNER:	THE DUKE ENDOWMENT
• REZONING SITE AREA:	1768 ACRES
• TAX PARCEL #:	120-053-10, 120-053-009
• EXISTING ZONING:	B-1
• PROPOSED ZONING:	MUDD-O
• EXISTING LAND USE:	VACANT COMMERCIAL BUILDING AND A PARTIALLY OCCUPIED COMMERCIAL BUILDING
• PROPOSED LAND USE:	OFFICE
• MAXIMUM BUILDING AREA:	BUILDING A: 47,500 SF BUILDING B: 37,000 SF
• MAXIMUM BUILDING HEIGHT:	BUILDING A: 62' AS MEASURED FROM MYRTLE AVE TO THE TOP OF THE STANDING SEAM METAL SCREEN MAXIMUM HEIGHT OF TOP OF PARAPET SHALL BE 47' AS MEASURED FROM MYRTLE AVE. BUILDING B: 62' AS MEASURED FROM ORIOLE AVE TO THE TOP OF THE STANDING SEAM METAL SCREEN MAXIMUM HEIGHT OF TOP OF PARAPET SHALL BE 47' AS MEASURED FROM ORIOLE AVE.
• PARKING:	REQUIRED: 1 SPACE PER 600 SQUARE FOOT OF BUILDING AREA AS REQUIRED BY MUDD ZONING PROVIDED: 1 SPACE PER 600 SQUARE FOOT OF BUILDING AREA AS REQUIRED BY MUDD ZONING
• OPEN SPACE:	MINIMUM 15% OF THE SITE WILL BE ESTABLISHED AS TREE SAVE AREA PER THE TREE ORDINANCE

DEVELOPMENT STANDARDS


- GENERAL PROVISIONS**
 - These Development Standards form a part of the Rezoning Plan associated with the Rezoning Petition filed by The Duke Endowment for an approximately 1,768 acre site located on the west side of East Morehead Street between Myrtle Avenue and Oriole Avenue, which site is more particularly depicted on the Rezoning Plan (hereinafter referred to as the "Site").
 - The development of the Site will be governed by the Rezoning Plan, these Development Standards and the applicable provisions of the City of Charlotte Zoning Ordinance (the "Ordinance"). Subject to the optional provision set out below, the regulations established under the Ordinance for the Mixed Use Development District ("MUDD") zoning district shall govern the development of the Site.
 - Future amendments to the Rezoning Plan and these Development Standards may be applied for by the then Owner or Owners of the Site in accordance with the provisions of Chapter 6 of the Ordinance.
- OPTIONAL PROVISIONS**

Petitioner requests the approval of the following optional provision:


 - The location of the vehicular driveway, three parallel parking spaces, a delivery space and the roll-out trash can and recycling enclosure between Building A and the required setbacks from Myrtle Avenue and East Morehead Street.
- PERMITTED USES**

The Site may be devoted only to professional business and general offices and to any incidental and accessory uses allowed in the MUDD zoning district, including, without limitation, conference rooms, meeting rooms and facilities, and a catering kitchen.
- TRANSPORTATION**
 - Vehicular access shall be as generally depicted on the Rezoning Plan. The placement and configuration of each access point are subject to any minor modifications required by the Charlotte Department of Transportation ("CDOT") and/or the North Carolina Department of Transportation ("NCDOT").
 - The driveway into the Site from East Morehead Street and Myrtle Avenue shall be a two-way driveway as depicted on the Rezoning Plan. However, if deemed necessary for the safety, mobility and efficiency of East Morehead Street and/or Myrtle Avenue by CDOT or NCDOT, Petitioner shall convert the driveway into a one-way driveway.
 - A minimum of 1 parking space per 600 square feet of gross floor area shall be provided on the Site. Notwithstanding the foregoing, the partially subterranean structured parking facility described below will contain a minimum of 130 parking spaces.
 - As depicted on the Rezoning Plan, and excepting the three parallel parking spaces noted above, the vehicular off-street parking spaces shall be located in a partially subterranean structured parking facility that will be accessed from Oriole Avenue.
 - Vehicles in the structured parking facility shall be screened from view from Oriole Avenue through the use of decorative or ornamental metal grillwork and supplemental screening plants.

- No openings into the structured parking facility shall be located on the western side of the structured parking facility except that openings for the ventilation of the structured parking facility shall be permitted. Any such openings for the ventilation of the structured parking facility shall include decorative or ornamental metal grillwork for screening.
 - Bicycle parking will be provided on the Site as required by the Ordinance.
 - Petitioner shall prohibit construction traffic serving the Site from utilizing Lexington Avenue to access the Site.
 - Petitioner shall prohibit construction vehicles serving the Site from parking on Lexington Avenue.
 - Petitioner shall make a formal request to CDOT to prohibit on-street parking along the Site's frontages on Myrtle Avenue and Oriole Avenue. This request shall be limited to the Site sides of Myrtle Avenue and Oriole Avenue.
 - Petitioner shall hire at least 1 off-duty law enforcement officer to manage traffic for any event at the Site.
- 1. MAXIMUM BUILDING AREA**
- As depicted on the Rezoning Plan, a maximum of two freestanding buildings and a structured parking facility may be constructed on the Site. The maximum gross floor area of that building designated as "Building A" on the Rezoning Plan shall be 47,500 square feet, and the maximum gross floor area of that building designated as "Building B" on the Rezoning Plan shall be 37,000 square feet.
 - The gross floor area of the structured parking facility shall not be counted towards the maximum gross floor area of Building A or Building B.
- 6. ARCHITECTURAL STANDARDS**
- The maximum height of Building A shall be 62 feet as measured from Myrtle Avenue to the top of the standing seam metal screen, and Building A may contain no more than 3 stories.
 - The maximum height of the top of the parapet of Building A shall be 47 feet as measured from Myrtle Avenue.
 - The standing seam metal screen shall be installed on Building A to screen mechanical equipment and similar building equipment and for aesthetic purposes. No habitable building floor area may be located above the roof deck of Building A (45 feet as measured from Myrtle Avenue).
 - The maximum height of Building B shall be 62 feet as measured from Oriole Avenue to the top of the standing seam metal screen, and Building B may contain no more than 3 stories.
 - The maximum height of the top of the parapet of Building B shall be 47 feet as measured from Oriole Avenue.
 - The standing seam metal screen shall be installed on Building B to screen mechanical equipment and similar building equipment and for aesthetic purposes. No habitable building floor area may be located above the roof deck of Building B (45 feet as measured from Oriole Avenue).
 - Attached to the Rezoning Plan are schematic architectural renderings of each elevation of Building A that are intended to depict the general architectural style, character and elements of each elevation of Building A. Accordingly, each elevation of Building A shall be designed and constructed so that it is substantially similar in appearance to the relevant schematic architectural renderings in terms of its architectural style, character and elements. Changes and alterations which do not materially change the overall conceptual architectural style and character are permitted based upon final design/construction drawings.
 - The minimum pitch or slope of the standing seam metal screen shall be 4:12 and the maximum pitch or slope shall be 10:12.
 - The permitted exterior building materials for Building A are set out on the attached schematic architectural renderings of Building A. More specifically, the permitted exterior building materials shall include bluestone, limestone, terracotta, a standing seam metal screen and glass.
 - Building B shall be compatible with Building A in appearance and quality through the use of similar architectural designs, styles and features, and similar building materials and colors.
 - The roll-out trash can and recycling area will be enclosed on all four sides by an opaque wall with hinged opaque gates or doors. If one or more sides of the roll-out trash can and recycling area are adjacent to a side wall or rear wall of a building, then the side wall or rear wall of the building may be substituted for the wall along each such side. Supplemental screening plants will be installed between the roll-out trash can and recycling area enclosure and Myrtle Avenue.
 - Attached to the Rezoning Plan is a schematic architectural rendering of the Myrtle Avenue elevation of the roll-out trash can and recycling area enclosure that is intended to depict the general architectural style, character and elements of the Myrtle Avenue elevation of the roll-out trash can and recycling area enclosure. Accordingly, the Myrtle Avenue elevation of the roll-out trash can and recycling area enclosure shall be designed and constructed so that it is substantially similar in appearance to the schematic architectural rendering in terms of its architectural style, character and elements. Changes and alterations which do not materially change the overall conceptual architectural style and character are permitted based upon final design/construction drawings.
 - Attached to the Rezoning Plan for illustrative purposes is a schematic plan that depicts the proposed landscaping to be installed adjacent to the roll-out trash can and recycling area enclosure. This plan is intended to portray the scale and the quantity of the landscaping to be installed adjacent to the roll-out trash can and recycling area enclosure. Modifications to the proposed landscaping may be approved by the Staff of the Charlotte-Mecklenburg Planning Department.
 - Attached to the Rezoning Plan for illustrative purposes are schematic plans of two potential design concepts for the driveway and open space area located on the Site at the intersection of East Morehead Street and Myrtle Avenue. These illustrative plans are intended to portray the scale, elements, features, character and quality of the driveway and open space area. Accordingly, portions of the driveway will contain pavers or stamped asphalt, and the open space area will contain landscaping, hardscape and seating. The water feature depicted on the illustrative plans shall not be required to be installed, but a water feature may be installed at the option of Petitioner. Changes and alterations that do not materially change the scale, elements, features, character and quality of the driveway and open space area are permitted based upon final design and construction drawings.
 - All roof mounted mechanical equipment will be screened from view from adjoining public rights-of-way and abutting properties as viewed from grade.
 - A green roof with planted materials shall be installed above the one story portion of Building A as depicted on the Rezoning Plan.
- 7. STREETScape and LANDSCAPING**
- Petitioner shall install a minimum 8 foot planting strip and a minimum 6 foot sidewalk along the Site's frontage on East Morehead Street.
 - Petitioner shall install a minimum 8 foot planting strip and a minimum 6 foot sidewalk along the Site's frontage on Oriole Avenue.
 - Petitioner shall install a minimum 8 foot planting strip and a minimum 6 foot sidewalk along the Site's frontage on Myrtle Avenue.
 - Internal sidewalks leading from Building A to Morehead Street and Myrtle Avenue shall be installed as generally depicted on the Rezoning Plan.
 - A 10 foot wide buffer/planting strip shall be installed along the western boundary line of the Site as depicted on the Rezoning Plan. This planting strip shall consist of a combination of evergreen trees and evergreen shrubs. Plant materials will be provided at a minimum rate of 6 trees and 20 shrubs per 100 linear feet in accordance with Sections 12.302(b),(c),(d), and (e) of the Ordinance.
 - The accessible path from the Urban Plaza may not be located within the 10 foot wide planting strip but shall be allowed to cross the 10 foot wide planting strip referenced above in subparagraph E to access the adjacent alley.
- 8. OPEN SPACE**
- The area designated on the Rezoning Plan as "Urban Plaza" shall be maintained as urban space and shall contain landscaping, horizontal hardscape, decorative and pedestrian scale lighting and outdoor seating.
 - That portion of the Site designated as the "Building B Building Area" on the Rezoning Plan shall be maintained as open space until such time that Building B is constructed, and this open space shall contain landscaping and/or detention facilities.
 - That portion of the Site located at the intersection of Myrtle Avenue and Morehead Street designated as open space shall contain landscaping, horizontal hardscape and outdoor seating.
- 9. SIGNAGE**
- All signs installed on the Site shall comply with the requirements of the Ordinance.
- 10. LIGHTING**
- All freestanding lighting fixtures installed on the Site (excluding street lights) shall be fully capped and shielded and the illumination downwardly directed so that direct illumination does not extend past any property line of the Site.
 - The maximum height of any freestanding lighting fixture installed on the Site shall be 20 feet.
 - Any lighting attached to the buildings to be located on the Site shall be decorative, capped and downwardly directed. "Wall-pak" type lighting fixtures may not be installed on the buildings to be located on the Site.
- 11. PHASING**
- The development of the Site will occur in two phases. Phase 1 will consist of all improvements depicted on the Rezoning Plan except for Building B. Building B will be constructed in Phase 2.
- 12. BRINDING EFFECT OF THE REZONING PETITION**
- If this Rezoning Petition is approved, all conditions applicable to the development and/or use of the Site imposed under this Rezoning Plan will, unless amended in the manner provided under the Ordinance, be binding upon and inure to the benefit of the Petitioner and the current and subsequent owners of the Site and their respective successors in interest and assigns. Throughout these Development Standards, the terms, "Petitioner" and "owner" or "owners" shall be deemed to include the heirs, devisees, personal representatives, successors in interest and assigns of Petitioner or the owner or owners of the Site from time to time who may be involved in any future development thereof.



GRAPHIC SCALE



800 East Morehead Street
Charlotte, NC 28203

214 North Tryon Street
Suite 2320
Charlotte NC 28202
Telephone 704.377.2725
Facsimile 704.377.2807

Gensler

STEWART
200 S COLLEGE ST
SUITE 720
CHARLOTTE, NC 28202
T 704.334.7925
F 704.334.7926
www.stewart-eng.com
Project No. X11023.00

**APPROVED BY
CITY COUNCIL**

JUL 16 2012

Date	Description
02.27.12	Rezoning Submittal
04.13.12	Revisions per Planning Staff Comments
06.22.12	Revisions per Planning Staff Comments
07.16.12	Revisions per Zoning Committee Comments

Seal/Signature

Project Name
THE DUKE ENDOWMENT

Project Number
59.6191.00

Description
REZONING PLAN

Scale
1" = 30'-0"

RZ 1.0

REVISED 04.13.12 - REZONING PETITION NUMBER 2012-044


STEWART
200 S COLLEGE ST
SUITE 720
CHARLOTTE, NC 28202
T 704.334.7925
F 704.334.7926
www.stewart-eng.com
Project No. X11023.00

**APPROVED BY
CITY COUNCIL**
JUL 16 2012


Date	Description
02.27.12	Rezoning Submittal
04.13.12	Revisions per Planning Staff Comments
06.22.12	Revisions per Planning Staff Comments




MYRTLE AVENUE ELEVATION
SCALE 1/16" = 1'-0"
1



ORIOLE AVENUE ELEVATION
SCALE 1/16" = 1'-0"
2



MOREHEAD STREET ELEVATION
SCALE 1/16" = 1'-0"
3



REAR ELEVATION
SCALE 1/16" = 1'-0"
4

REVISED 06.22.12 - REZONING PETITION NUMBER 2012-044

Seal/Signature


Project Name
THE DUKE ENDOWMENT

Project Number
58.6191.00


Description
REZONING PLAN

Scale
1" = 30'-0"


RZ 2.0



ROLL-OUT TRASH ENCLOSURE ELEVATION
SCALE: 1/8" = 1'-0"
1



ROLL-OUT TRASH ENCLOSURE LANDSCAPE PLAN
NOT TO SCALE
2



ENTRY PLAZA CONCEPTS
SCALE: 1/8" = 1'-0"
3

800 East Morehead Street
Charlotte, NC 28203

214 North Tryon Street
Suite 2320
Charlotte, NC 28202
Telephone 704.377.2725
Facsimile 704.377.2807

Gensler

STEWART-ENG
200 S COLLEGE ST
SUITE 720
CHARLOTTE, NC 28202
T 704.334.7925
F 704.334.7926
www.stewart-eng.com
Project No. X11023.00

©2012. All documents and calculations including graphics, drawings, and specifications prepared by Stewart-Eng, Inc. are the property of Stewart-Eng, Inc. and are to be used only for the project and site specified. Any other use without the written consent of Stewart-Eng, Inc. is prohibited. This document is the property of Stewart-Eng, Inc. and is not to be distributed, copied, or otherwise used without the written consent of Stewart-Eng, Inc.

**APPROVED BY
CITY COUNCIL**
JUL 16 2012

Date	Description
02.27.12	Rezoning Submittal
04.13.12	Revisions per Planning Staff Comments
06.22.12	Revisions per Planning Staff Comments

REVISED 06.22.12 - REZONING PETITION NUMBER 2012-044

Seal/Signature _____

Project Name
THE DUKE ENDOWMENT

Project Number
59.6191.00

Description
REZONING PLAN

Scale
1" = 30'-0"