


PAM ROBERSON
DB 29040 PG 707
TAX ID 065-045-06

ROBERT FRITTS
LAURA FRITTS
DB 21704 PG 116
TAX ID 065-045-02

SCOTT SHELTON
DB 18070 PG 262
TAX ID 065-045-15



1 Conditional Rezoning Site Plan

Scale: 1" = 15'

1. **DEVELOPMENT DATA TABLE**
 - A. SITE ACREAGE - 0.268 ACRES
 - B. TAX PARCEL ID - 065-045-01
 - C. EXISTING ZONING - B-1 (BUSINESS)
 - D. PROPOSED ZONING - MUDD-O (MIXED USE DEVELOPMENT DISTRICT)
 - E. NUMBER OF RESIDENTIAL UNITS - NONE
 - F. RESIDENTIAL DENSITY - NONE
 - G. SQUARE FOOTAGE OF NON RESIDENTIAL USES BY TYPE - 4,480 SF - BAR & LOUNGE
 - H. FLOOR AREA RATIO - 0.384
 - I. MAXIMUM BUILDING HEIGHT - 22 FEET
 - J. MAXIMUM NUMBER OF BUILDINGS - ONE
 - K. PARKING PROVIDED PER THE CHARLOTTE ZONING ORDINANCE
 - L. AMOUNT OF OPEN SPACE - 0.08 ACRES
2. **GENERAL PROVISIONS**
 - A. THE DEVELOPMENT SHALL ADHERE TO THE ALL CITY OF CHARLOTTE, MECKLENBURG COUNTY AND THE STATE OF NORTH CAROLINA ORDINANCES AND CODES.
 - B. ALL ALTERATIONS TO THIS CONDITIONAL PLAN ARE SUBJECT TO THE CHARLOTTE ZONING ORDINANCE SECTION 6.207 ALTERATIONS TO APPROVAL.
 - C. A 6-FOOT PRIVACY FENCE SHALL BE LOCATED ALONG THE REAR PROPERTY LINE ADJACENT TO THE RESIDENTIAL USE. THE FENCE SHALL BE CONSTRUCTED OF WOOD, BRICK, STONE OR VINYL COMPOSITE.
3. **OPTIONAL PROVISIONS**
 - A. PARKING AND MANEUVERING SHALL BE ALLOWED BETWEEN THE BUILDING, TUCKASEEGEE ROAD AND ENDERLY ROAD.
 - B. THE DEVELOPMENT SHALL NOT BE REQUIRED TO COMPLY WITH SECTION 9.8506(2)(a) OF THE CHARLOTTE ZONING ORDINANCE REGULATING BUILDING STREET WALLS.
4. **PERMITTED USES**
 - A. THE PROPERTY CAN BE USED FOR ALL USES PERMITTED BY RIGHT AS PER THE CHARLOTTE ZONING ORDINANCE FOR MUDD (MIXED USE DEVELOPMENT DISTRICT) OCCUPANCIES WITH THE EXCEPTION OF
 - 4.1 ANIMAL CREMATORIUM
 - 4.2 AUTOMOTIVE SERVICE STATIONS
 - 4.3 BUS & TRAIN TERMINALS
 - 4.4 ADULT ESTABLISHMENTS
 - 4.5 BUS PASSENGER STATIONS
 - 4.6 COLLEGES, UNIVERSITIES, COMMERCIAL SCHOOLS, AND SCHOOLS PROVIDING ADULT TRAINING
 - 4.7 DORMITORIES
 - 4.8 EQUIPMENT RENTAL AND LEASING WITHIN AN ENCLOSED BUILDING
 - 4.9 HOTELS AND MOTELS
 - 4.10 DENTAL, MEDICAL AND OPTICAL LABORATORIES
 - 4.11 LABORATORIES WITHIN AN ENCLOSED BUILDING FOR APPLIED AND BASIC RESEARCH
 - 4.12 WAREHOUSING WITHIN AN ENCLOSED BUILDING FOR SELF STORAGE FACILITY
 - B. NO OTHER USE RESTRICTIONS ARE APPLICABLE
5. **TRANSPORTATION**
 - A. A MINIMUM OF 36 FEET OF STREET RIGHT OF WAY FROM THE EXISTING ENDERLY ROAD CENTERLINE AS PER THE CHARLOTTE LAND DEVELOPMENT STANDARDS MANUAL (CLDSM) STANDARD DETAIL U-07 - LOCAL COLLECTOR STREET TYPICAL SECTION SHALL BE DEDICATED.
 - B. A 6-FOOT SIDEWALK SHALL BE CONSTRUCTED AT THE PROPERTY FRONTAGE ALONG ENDERLY ROAD PER SECTION 11.507, STREETScape REQUIREMENTS OF CHAPTER 11 OF THE CHARLOTTE ZONING ORDINANCE.
 - C. A MINIMUM 8-FOOT PLANTING STRIP SHALL BE PROVIDED AT THE PROPERTY FRONTAGE ALONG ENDERLY ROAD.
 - D. A MINIMUM OF 40 FEET OF STREET RIGHT OF WAY FROM THE EXISTING TUCKASEEGEE ROAD CENTERLINE PER THE 2004 MECKLENBURG-UNION METROPOLITAN PLANNING ORGANIZATION THOROUGHFARE PLAN FOR A MAJOR THOROUGHFARE INSIDE OF ROUTE 4, SHALL BE DEDICATED.
 - E. A PROPOSED 26'-0" MODIFIED TYPE II DRIVEWAY PER THE CHARLOTTE LAND DEVELOPMENT STANDARDS MANUAL (CLDSM) STANDARD DETAIL 10.25E - MODIFIED TYPE II DRIVEWAY DETAIL WITH PLANTING STRIP SHALL BE CONSTRUCTED.
 - F. THE EXISTING CURB RAMP AT THE SOUTHWEST CORNER OF THE INTERSECTION OF TUCKASEEGEE ROAD AND ENDERLY ROAD SHALL BE REPLACED WITH DIRECTIONAL RAMPS PER THE CHARLOTTE LAND DEVELOPMENT STANDARDS MANUAL (CLDSM) STANDARD DETAILS A-C, DIRECTIONAL CURB RAMPS.
 - G. ALL RIGHT OF WAY DEDICATION AND FEE SIMPLE CONVEYANCE TO THE CITY OF CHARLOTTE SHALL BE COMPLETED PRIOR TO THE ISSUANCE OF A CERTIFICATE OF OCCUPANCY FOR THE BUILDING.
 - H. ALL TRANSPORTATION IMPROVEMENTS SHALL BE APPROVED AND CONSTRUCTED PRIOR TO THE ISSUANCE OF A CERTIFICATE OF OCCUPANCY FOR THE BUILDING.
6. **ARCHITECTURAL STANDARDS**
 - A. THE BUILDING IS CURRENTLY CONSTRUCTED WITH A BRICK VENEER
 - B. THE BUILDING SIZE AND HEIGHT ARE EXISTING AND SHALL REMAIN.
 - C. OLD METAL DOORS AND WINDOWS WILL BE REPLACED WITH NEW ALUMINUM STOREFRONT WINDOORS AND WINDOWS.
 - D. A WOODEN PRIVACY SCREEN FENCE WILL BE PROVIDED TO ADHERE TO THE BUFFER REQUIREMENTS OF THE CITY OF CHARLOTTE ZONING ORDINANCE (CZO).
7. **STREETScape AND LANDSCAPING**
 - A. THE STREETScape ALONG TUCKASEEGEE ROAD SHALL CONSIST OF A 6-FOOT SIDEWALK AND AN 8-FOOT PLANTING STRIP. THE STREETScape ALONG ENDERLY ROAD SHALL CONSIST OF A 6-FOOT SIDEWALK AND A 8-FOOT PLANTING STRIP.
 - B. NO SPECIAL LANDSCAPE, BUFFER, SCREENING TREATMENT SHALL BE PROVIDED. SCREENING AND BUFFERS SHALL BE PROVIDED AS REQUIRED PER THE CZO.
8. **ENVIRONMENTAL FEATURES**
 - A. THE PETITIONER SHALL COMPLY WITH THE CHARLOTTE CITY COUNCIL APPROVED AND ADOPTED POST CONSTRUCTION STORMWATER ORDINANCE.
9. **PARKS, GREENWAYS, AND OPEN SPACE**
 - A. NOT APPLICABLE
 - B. NOT APPLICABLE
 - C. NOT APPLICABLE
 - D. NOT APPLICABLE
10. **FIRE PROTECTION**
 - A. NOT APPLICABLE
11. **SIGNAGE**
 - A. THE BUILDING SIGNAGE SHALL ADHERE TO THE REQUIREMENTS OF THE CITY OF CHARLOTTE SIGN ORDINANCE.
12. **LIGHTING**
 - A. LIGHTING SHALL BE PROVIDED AS REQUIRED AT BUILDING EGRESS POINTS AND FOR SECURE ACCESS TO THE PARKING.
 - B. LIGHTING SHALL BE PROVIDED AT A SCALE AND ILLUMINATION TO ENHANCE THE NEIGHBORHOOD AND TO NOT PRODUCE INTRUSION UPON ADJACENT RESIDENTIAL NEIGHBORS.
 - C. ALL LIGHTING SHALL BE FULLY CAPPED AND SHIELDED. LIGHTING SHALL BE DOWNWARDLY DIRECTED SO THAT DIRECT ILLUMINATION DOES NOT EXTEND PAST ANY PROPERTY LINE OF THE SITE.
13. **PHASING**
 - A. THE PROPERTY WILL NOT BE RENOVATED IN PHASES.
14. **OTHER**
 - A. THERE WILL BE NO REQUEST FOR RIGHT OF WAY ENHANCEMENTS OR FOR A VARIANCE FOR THIS PROPERTY
 - B. THE BUILDING IS EXISTING AND PROPERTY CORNER TIE POINTS SHOULD NOT BE REQUIRED.
 - C. THERE WILL BE NO PUBLIC FACILITIES OR SITES PROVIDED
 - D. THE PROPOSED DUMPSTER SHALL BE LOCATED AT THE REAR OF THE PROPERTY
 - E. NO PUBLIC ART SHALL BE PROVIDED
 - F. A NEW FIRE LINE SHALL BE EXTENDED TO THE BUILDING. NO OTHER UNDERGROUND UTILITIES SHALL BE ADDED.
 - G. NO ADDITIONAL CONDITIONS
 - H. THE PETITIONERS SHALL PRESERVE THE EXISTING BUILDING ON SITE.
 - I. SOLID WASTE REMOVAL WILL OCCUR OUTSIDE OF HOURS OF OPERATION.



CSE
ENGINEERING
CONSULTANTS
8511 Davis Lake Parkway
Suite C5-200
Charlotte, NC 28269
704-595-5428

This document and all of its contents are the property of CSE Engineering Consultants PLLC and shall not be used, reproduced or duplicated in part or in whole without the written consent of CSE Engineering Consultants PLLC.
Copyright ©
CSE Engineering Consultants PLLC


Conditional Rezoning Site Plan
The Marquee Tapas & Lounge
3131 Tuckasegee Road
Charlotte, NC 28208

REVISIONS	
NO.	DATE
1	12/18/19
2	01/08/20
3	02/24/20
4	02/27/20

By	CSE
Checked	CSE
Drawn	CSE
Designed	CSE
Reviewed	CSE
Author	KAK

Project No. 19-597-01
Sheet No. RZ1.0

Charlotte
Planning Department
APPROVED BY CITY COUNCIL
March 16, 2020



VICINITY MAP

CSE
ENGINEERING
CONSULTANTS
8511 Davis Lake Parkway
Suite C6-200
Charlotte, NC 28269
704-509-5828



This document and all of its interdependencies are the property of CSE Engineering Consultants PLLC and shall not be used, reproduced or duplicated in part or in whole without the written consent of CSE Engineering Consultants PLLC.
© Copyright
CSE Engineering Consultants PLLC

Conditional Rezoning Site Plan
The Marquee Tapas & Lounge
3131 Tuckasee Road
Charlotte, NC 28208

REVISIONS	
NO.	DESCRIPTION
1	AS NOTED

Project No. 19-597-01
Sheet No.

RZ1.1



1 Conditional Rezoning Site Plan - Garbage Truck Movement Path
Scale: 1" = 15'