

Access Compliance Report

Public Rights-of-Way

(Curb Ramps)

Intersection ID: 53380	Main Street: IKEA_BV	Cross Street: LEWIS_ST	Location: E
ADA ID: 0C66D142D60E	Ramp Type: Directional1	Initial Pass/Fail: Pass	Overall Compliance: No
Severity Score: 7.5			
Codes/Mitigation Info/Possible Solution		Field Measurements/Component Compliance	



Possible Solutions:

Remove & Replace Entire Ramp.

Surveyor Notes:

N/A

PROW/ADA:

Not Found, R304.5.3, R304.5.2, R302.7.2

Total Cost: \$ 1600.00

Compliance	Description	Data	Compliance	Description	Data
N/A	Ramp Length (in)	77.0	No	Grade Break?	No
Yes	Ramp Width (in)	93.0	N/A	Grade Break Slope (%)	N/A
Yes	Ramp Slope (%)	6.7	N/A	Grade Break XSlope (%)	N/A
Yes	Ramp XSlope (%)	0.8			
Yes	Flare Type LT	N/A	Yes	Flare Type RT	N/A
N/A	Flare Slope LT (%)	N/A	N/A	Flare Slope RT (%)	N/A
N/A	Flare Traversable LT?	No	N/A	Flare Traversable RT?	No
Yes	Landing Length (in)	69.0	Yes	DWS Provided?	Yes
Yes	Landing Width (in)	93.0	Yes	DWS Contrast?	Yes
Yes	Landing Slope (%)	0.2	Yes	DWS Length (in)	24.0
No	Landing X Slope (%)	3.8	Yes	DWS Full Width?	Yes
N/A	Landing Curb? (Y/N)	N/A	Yes	DWS Offset LT (in)	1.5
N/A	Shared Landing?	No	Yes	DWS Offset RT (in)	1.0
Yes	Gutter Ponding?	No	Yes	Gutter Slope (%)	1.0
No	Gutter Lip Ht (in)	0.3	Yes	Gutter X Slope (%)	0.8
N/A	Painted X Walk1?	Yes		Road Slope (%)	2.9
	X Walk 1 Direction	To SW		Road X Slope (%)	3.0
	X Walk 1 Width (in)	94.0		Clear Space?	Yes
	X Walk 1 Slope (%)	2.9	N/A	Clear Space to XWalk (in)	N/A
	X Walk 1 X Slope (%)	3.0	Yes	Storm Grate/Utility Hazard?	No
Yes	Ramp inside XWalk1?	Yes		Storm Grate/Utility Type	
Yes	Any Obstructions?	No			N/A
	Obstruction Type		Yes	Surface Condition? (G/P)	Good
			N/A	Curb Slope (%)	19.4

Street 1 Name LEWIS ST
 Stop Condition-Street 1 StopSign
 Street 2 Name N/A
 Stop Condition-Street 2 N/A

