

Access Compliance Report

Public Rights-of-Way

(Curb Ramps)

Intersection ID: 16310	Main Street: LYNNVILLE_AV	Cross Street: N_SHARON_AMITY_RD	Location: NW
ADA ID: 1B3A1645157B	Ramp Type: ParaDiag	Initial Pass/Fail: Pass	Overall Compliance: No
			Severity Score: 10.25

Codes/Mitigation Info/Possible Solution

Field Measurements/Component Compliance



Possible Solutions:

Remove & Replace Curb Ramp With Two New Directional Ramps or Equivalent. Gutter Ponding Observed.

Surveyor Notes:

RT RP < 5%

PROW/ADA:

R304.5.3, R304.2.1, R304.2.2-Perp, R304.3.2-Para, R305, R302.7

Total Cost: \$ 3700.00

Compliance	Description	Data	Compliance	Description	Data
N/A	Ramp Length LT (in)	55.0	N/A	Ramp Length RT (in)	48.0
Yes	Ramp Width LT (in)	75.0	Yes	Ramp Width RT (in)	71.0
Yes	Ramp Slope LT (%)	7.4	Yes	Ramp Slope RT (%)	4.7
No	Ramp XSlope LT (%)	3.7	No	Ramp XSlope RT (%)	2.7
Yes	Landing Length (in)	77.0	No	DWS Provided?	No
No	Landing Width (in)	35.0	N/A	DWS Contrast?	No
No	Landing Slope (%)	3.0	N/A	DWS Length (in)	N/A
Yes	Landing X Slope (%)	1.0	N/A	DWS Full Width?	No
N/A	Landing Curb? (Y/N)	No	N/A	DWS Offset (in)	N/A
N/A	Shared Landing?	No			
No	Gutter Ponding?	Yes	Yes	Gutter Slope (%)	1.5
Yes	Gutter Lip Ht (in)	0.0	Yes	Gutter X Slope (%)	0.7
N/A	Painted X Walk1?	No	N/A	Painted X Walk2?	No
	X Walk 1 Direction	To SE		X Walk 2 Direction	To NE
N/A	X Walk 1 Width (in)	N/A	N/A	X Walk 2 Width (in)	N/A
	X Walk 1 Slope (%)	1.4		X Walk 2 Slope (%)	2.3
	X Walk 1 X Slope (%)	3.0		X Walk 2 X Slope (%)	2.1
N/A	Ramp inside XWalk1?	N/A	N/A	Ramp inside XWalk2?	N/A
	Road Slope (%)	0.1	N/A	Clear Space?	Yes
	Road X Slope (%)	3.6	N/A	Clear Space to XWalk (in)	N/A
Yes	Any Obstructions?	No	Yes	Storm Grate/Utility Hazard?	No
	Obstruction Type			Storm Grate/Utility Type	
		N/A			N/A
			Yes	Surface Condition? (G/P)	Good
			N/A	Curb Slope (%)	8.8

Street 1 Name N SHARON AMITY RD
 Stop Condition-Street 1 None
 Street 2 Name LYNNVILLE AV
 Stop Condition-Street 2 StopSign

