

Access Compliance Report

Public Rights-of-Way

(Curb Ramps)

Intersection ID: 27490	Main Street: BALLANTYNE COMMONS PY	Cross Street: JOHNSTON RD	Location: SE
ADA ID: 88029725B00E	Ramp Type: Directional1	Initial Pass/Fail: Pass	Overall Compliance: No
Codes/Mitigation Info/Possible Solution			Severity Score: 7.5
			Field Measurements/Component Compliance



Possible Solutions:

Remove & Replace Detectable Warning System. Remove & Replace Gutter.

Surveyor Notes:

NO CURB LINE

PROW/ADA:

R305.2, R302.7.2, R304.5.3

Total Cost: \$ 1550.00

Compliance	Description	Data	Compliance	Description	Data
N/A	Ramp Length (in)	77.5	Yes	Grade Break?	Yes
Yes	Ramp Width (in)	71.5	Yes	Grade Break Slope (%)	4.3
Yes	Ramp Slope (%)	4.7	Yes	Grade Break XSlope (%)	2.3
Yes	Ramp XSlope (%)	0.9			
N/A	Flare Type LT	N/A	N/A	Flare Type RT	N/A
N/A	Flare Slope LT (%)	N/A	N/A	Flare Slope RT (%)	N/A
N/A	Flare Traversable LT?	N/A	N/A	Flare Traversable RT?	N/A
Yes	Landing Length (in)	58.0	Yes	DWS Provided?	Yes
Yes	Landing Width (in)	71.5	Yes	DWS Contrast?	Yes
Yes	Landing Slope (%)	1.5	Yes	DWS Length (in)	24.5
Yes	Landing X Slope (%)	0.4	Yes	DWS Full Width?	Yes
N/A	Landing Curb? (Y/N)	No	Yes	DWS Offset LT (in)	47.0
N/A	Shared Landing?	No	No	DWS Offset RT (in)	7.0
Yes	Gutter Ponding?	No	Yes	Gutter Slope (%)	0.2
No	Gutter Lip Ht (in)	0.3	No	Gutter X Slope (%)	3.4
N/A	Painted X Walk1?	Yes		Road Slope (%)	1.6
	X Walk 1 Direction	To N		Road X Slope (%)	2.6
	X Walk 1 Width (in)	121.0		Clear Space?	Yes
	X Walk 1 Slope (%)	1.6	N/A	Clear Space to XWalk (in)	N/A
	X Walk 1 X Slope (%)	2.6	Yes	Storm Grate/Utility Hazard?	No
Yes	Ramp inside XWalk1?	Yes		Storm Grate/Utility Type	
Yes	Any Obstructions?	No			N/A
	Obstruction Type		Yes	Surface Condition? (G/P)	Good
			N/A	Curb Slope (%)	N/A

Street 1 Name BALLANTYNE COMMONS PY
 Stop Condition-Street 1 Signal
 Street 2 Name N/A
 Stop Condition-Street 2 N/A

