

# Access Compliance Report

## Public Rights-of-Way

### (Curb Ramps)

Intersection ID: 10021758	Main Street: BRIARWICK_LN	Cross Street: SCOUTS_WY	Location: SW
ADA ID: 8B8518D5D265	Ramp Type: Perp	Initial Pass/Fail: Pass	Overall Compliance: No
Severity Score: 15			
Codes/Mitigation Info/Possible Solution		Field Measurements/Component Compliance	



Possible Solutions:

**Remove & Replace Detectable Warning System. Grind Gutter Lip.**

Surveyor Notes:

**N/A**

PROW/ADA:

**R305.2, R302.7, R302.7.2**

Total Cost: \$ 1000.00

Compliance	Description	Data	Compliance	Description	Data
N/A	Ramp Length (in)	94.5	Yes	Ramp Slope (%)	6.8
Yes	Ramp Width (in)	58.0	Yes	Ramp XSlope (%)	0.2
N/A	Flare Type LT	Sloped	N/A	Flare Type RT	N/A
N/A	Flare Slope LT (%)	1.4	Yes	Flare Slope RT (%)	2.2
N/A	Flare Traversable LT?	Yes	N/A	Flare Traversable RT?	Yes
Yes	Landing Length (in)	58.0	Yes	DWS Provided?	Yes
Yes	Landing Width (in)	60.0	Yes	DWS Contrast?	Yes
Yes	Landing Slope (%)	1.3	Yes	DWS Length (in)	24.5
Yes	Landing X Slope (%)	1.9	Yes	DWS Full Width?	Yes
N/A	Landing Curb? (Y/N)	No	No	DWS Offset (in)	4.0
N/A	Shared Landing?	No			
No	Gutter Ponding?	Yes	Yes	Gutter Slope (%)	1.4
No	Gutter Lip Ht (in)	1.0	Yes	Gutter X Slope (%)	0.4
N/A	Painted X Walk1?	No	N/A	Painted X Walk2?	N/A
	X Walk 1 Direction	To N		X Walk 2 Direction	N/A
N/A	X Walk 1 Width (in)	N/A	N/A	X Walk 2 Width (in)	N/A
	X Walk 1 Slope (%)	4.0		X Walk 2 Slope (%)	N/A
	X Walk 1 X Slope (%)	2.8		X Walk 2 X Slope (%)	N/A
N/A	Ramp inside XWalk1?	N/A	N/A	Ramp inside XWalk2?	N/A
	Road Slope (%)	N/A	N/A	Clear Space?	Yes
	Road X Slope (%)	N/A	N/A	Clear Space to XWalk (in)	N/A
Yes	Any Obstructions?	No	Yes	Storm Grate/Utility Hazard?	No
	Obstruction Type			Storm Grate/Utility Type	
		N/A			N/A
			Yes	Surface Condition? (G/P)	Good

