

# Access Compliance Report

## Public Rights-of-Way

### (Curb Ramps)

Intersection ID: 12003	Main Street: N_TRYON_ST	Cross Street: E_7TH_ST	Location: S
ADA ID: A7E86ADC8834	Ramp Type: PerpDiag	Initial Pass/Fail: Pass	Overall Compliance: No
Codes/Mitigation Info/Possible Solution		Field Measurements/Component Compliance	
Severity Score: 7.75			



Possible Solutions:

**Remove & Replace Curb Ramp With Two New Directional Ramps or Equivalent. Restripe Crosswalk(s) To Provide Clear space. Remove & Replace Gutter.**

Surveyor Notes:

N/A

PROW/ADA:

**R304.5.3, R304.2.2-Perp, R304.3.2-Para, Not Found, R305.1.4, R304.5.4**

Total Cost: \$ 4450.00

Compliance	Description	Data	Compliance	Description	Data
N/A	Ramp Length (in)	96.0	Yes	Ramp Slope (%)	8.3
Yes	Ramp Width (in)	68.0	No	Ramp XSlope (%)	5.0
N/A	Flare Type LT	Sloped	N/A	Flare Type RT	N/A
N/A	Flare Slope LT (%)	7.5	Yes	Flare Slope RT (%)	9.3
N/A	Flare Traversable LT?	Yes	N/A	Flare Traversable RT?	Yes
Yes	Landing Length (in)	60.0	Yes	DWS Provided?	Yes
Yes	Landing Width (in)	60.0	Yes	DWS Contrast?	Yes
No	Landing Slope (%)	4.0	Yes	DWS Length (in)	24.0
Yes	Landing X Slope (%)	1.4	No	DWS Full Width?	No
N/A	Landing Curb? (Y/N)	No	Yes	DWS Offset (in)	0.0
N/A	Shared Landing?	No			
Yes	Gutter Ponding?	No	No	Gutter Slope (%)	5.4
Yes	Gutter Lip Ht (in)	0.0	Yes	Gutter X Slope (%)	0.8
N/A	Painted X Walk1?	Yes	N/A	Painted X Walk2?	Yes
	X Walk 1 Direction	To NE		X Walk 2 Direction	To NW
N/A	X Walk 1 Width (in)	113.0	N/A	X Walk 2 Width (in)	103.0
	X Walk 1 Slope (%)	0.1		X Walk 2 Slope (%)	3.6
	X Walk 1 X Slope (%)	0.1		X Walk 2 X Slope (%)	3.9
Yes	Ramp inside XWalk1?	Yes	Yes	Ramp inside XWalk2?	Yes
	Road Slope (%)	2.8	N/A	Clear Space?	Yes
	Road X Slope (%)	1.8	No	Clear Space to XWalk (in)	42.0
Yes	Any Obstructions?	No	Yes	Storm Grate/Utility Hazard?	No
	Obstruction Type			Storm Grate/Utility Type	
		N/A			N/A
			Yes	Surface Condition? (G/P)	Good

