

Access Compliance Report

Public Rights-of-Way

(Curb Ramps)

| | | | |
|---|--------------------------|---|------------------------|
| Intersection ID: 11891 | Main Street: N_POPLAR_ST | Cross Street: W_6TH_ST | Location: S |
| ADA ID: B903FAB5C9FD | Ramp Type: PerpDiag | Initial Pass/Fail: Pass | Overall Compliance: No |
| Codes/Mitigation Info/Possible Solution | | Field Measurements/Component Compliance | |



Possible Solutions:

Remove & Replace Curb Ramp With Two New Directional Ramps or Equivalent. Restripe Crosswalk(s) To Provide Clear space. Remove & Replace Gutter.

Surveyor Notes:

N/A

PROW/ADA:

Not Found, R304.2.2, R304.2.1, R304.2.2-Perp, R304.3.2-Para, R304.5.3, R305

Total Cost: \$ 4450.00

| Compliance | Description | Data | Compliance | Description | Data |
|------------|-----------------------|--------|------------|-----------------------------|-------|
| N/A | Ramp Length (in) | 72.0 | No | Ramp Slope (%) | 9.3 |
| Yes | Ramp Width (in) | 60.0 | Yes | Ramp XSlope (%) | 2.8 |
| N/A | Flare Type LT | Sloped | N/A | Flare Type RT | N/A |
| N/A | Flare Slope LT (%) | 1.6 | N/A | Flare Slope RT (%) | 9.9 |
| N/A | Flare Traversable LT? | Yes | N/A | Flare Traversable RT? | No |
| No | Landing Length (in) | N/A | No | DWS Provided? | No |
| No | Landing Width (in) | N/A | N/A | DWS Contrast? | No |
| No | Landing Slope (%) | N/A | N/A | DWS Length (in) | N/A |
| No | Landing X Slope (%) | N/A | N/A | DWS Full Width? | No |
| N/A | Landing Curb? (Y/N) | No | N/A | DWS Offset (in) | N/A |
| N/A | Shared Landing? | No | | | |
| Yes | Gutter Ponding? | No | Yes | Gutter Slope (%) | 2.0 |
| Yes | Gutter Lip Ht (in) | 0.0 | No | Gutter X Slope (%) | 4.9 |
| N/A | Painted X Walk1? | Yes | N/A | Painted X Walk2? | Yes |
| | X Walk 1 Direction | To NW | | X Walk 2 Direction | To NE |
| N/A | X Walk 1 Width (in) | 136.0 | N/A | X Walk 2 Width (in) | 137.0 |
| | X Walk 1 Slope (%) | 1.4 | | X Walk 2 Slope (%) | 1.4 |
| | X Walk 1 X Slope (%) | 1.1 | | X Walk 2 X Slope (%) | 1.0 |
| Yes | Ramp inside XWalk1? | Yes | Yes | Ramp inside XWalk2? | Yes |
| | Road Slope (%) | 3.9 | N/A | Clear Space? | Yes |
| | Road X Slope (%) | 0.6 | No | Clear Space to XWalk (in) | 30.0 |
| Yes | Any Obstructions? | No | Yes | Storm Grate/Utility Hazard? | No |
| | Obstruction Type | | | Storm Grate/Utility Type | |
| | | N/A | | | N/A |
| | | | Yes | Surface Condition? (G/P) | Good |

