

# Access Compliance Report

## Public Rights-of-Way

### (Curb Ramps)

|                        |                        |                                       |                        |
|------------------------|------------------------|---------------------------------------|------------------------|
| Intersection ID: 54364 | Main Street: GANNON_DR | Cross Street: BEREWICK_TOWN_CENTER_DR | Location: N            |
| ADA ID: D1FFCA7548BD   | Ramp Type: Perp        | Initial Pass/Fail: Pass               | Overall Compliance: No |
|                        |                        | Severity Score: 0                     |                        |

#### Codes/Mitigation Info/Possible Solution

#### Field Measurements/Component Compliance



Possible Solutions:

**Remove & Replace Entire Ramp.**

Surveyor Notes:

**N/A**

PROW/ADA:

**Not Found**

Total Cost: \$ 1850.00

| Compliance | Description           | Data                 | Compliance | Description                 | Data |
|------------|-----------------------|----------------------|------------|-----------------------------|------|
| N/A        | Ramp Length (in)      | 75.0                 | Yes        | Ramp Slope (%)              | 5.8  |
| Yes        | Ramp Width (in)       | 93.0                 | Yes        | Ramp XSlope (%)             | 0.5  |
| Yes        | Flare Type L          | Curbed_NoWalkSurface | Yes        | Flare Type RT               | N/A  |
| Yes        | Flare Slope LT (%)    | N/A                  | N/A        | Flare Slope RT (%)          | N/A  |
| N/A        | Flare Traversable LT? | No                   | N/A        | Flare Traversable RT?       | No   |
| Yes        | Landing Length (in)   | 65.0                 | Yes        | DWS Provided?               | Yes  |
| Yes        | Landing Width (in)    | 93.0                 | Yes        | DWS Contrast?               | Yes  |
| Yes        | Landing Slope (%)     | 2.0                  | Yes        | DWS Length (in)             | 24.0 |
| Yes        | Landing X Slope (%)   | 0.1                  | Yes        | DWS Full Width?             | Yes  |
| N/A        | Landing Curb? (Y/N)   | No                   | Yes        | DWS Offset (in)             | 0.0  |
| N/A        | Shared Landing?       | No                   |            |                             |      |
| Yes        | Gutter Ponding?       | No                   | Yes        | Gutter Slope (%)            | 1.5  |
| Yes        | Gutter Lip Ht (in)    | 0.0                  | Yes        | Gutter X Slope (%)          | 1.3  |
| N/A        | Painted X Walk1?      | Yes                  | N/A        | Painted X Walk2?            | N/A  |
|            | X Walk 1 Direction    | To SE                |            | X Walk 2 Direction          | N/A  |
| N/A        | X Walk 1 Width (in)   | 97.5                 | N/A        | X Walk 2 Width (in)         | N/A  |
|            | X Walk 1 Slope (%)    | 2.8                  |            | X Walk 2 Slope (%)          | N/A  |
|            | X Walk 1 X Slope (%)  | 1.4                  |            | X Walk 2 X Slope (%)        | N/A  |
| Yes        | Ramp inside XWalk1?   | Yes                  | N/A        | Ramp inside XWalk2?         | N/A  |
|            | Road Slope (%)        | N/A                  | N/A        | Clear Space?                | Yes  |
|            | Road X Slope (%)      | N/A                  | N/A        | Clear Space to XWalk (in)   | N/A  |
| Yes        | Any Obstructions?     | No                   | Yes        | Storm Grate/Utility Hazard? | No   |
|            | Obstruction Type      |                      |            | Storm Grate/Utility Type    |      |
|            |                       | N/A                  |            |                             | N/A  |
|            |                       |                      | Yes        | Surface Condition? (G/P)    | Good |

