

Access Compliance Report

Public Rights-of-Way (Curb Ramps)

Intersection ID: 15882	Main Street: EAST_BV	Cross Street: QUEENS_RD_WEST	Location: W
ADA ID: FDF88DFC0ED2	Ramp Type: Directional1	Initial Pass/Fail: Pass	Overall Compliance: No
Severity Score: 2.75			
Codes/Mitigation Info/Possible Solution		Field Measurements/Component Compliance	



Possible Solutions:

Remove & Replace Entire Ramp.

Surveyor Notes:

N/A

PROW/ADA:

**R304.5.3, R304.2.1, R304.5.2,
R305.1.4**

Total Cost: \$ 1600.00

Compliance	Description	Data	Compliance	Description	Data
N/A	Ramp Length (in)	77.0	No	Grade Break?	No
Yes	Ramp Width (in)	48.0	N/A	Grade Break Slope (%)	6.2
Yes	Ramp Slope (%)	5.3	N/A	Grade Break XSlope (%)	0.1
No	Ramp XSlope (%)	3.1			
N/A	Flare Type LT	N/A	N/A	Flare Type RT	N/A
N/A	Flare Slope LT (%)	6.2	N/A	Flare Slope RT (%)	5.6
N/A	Flare Traversable LT?	No	N/A	Flare Traversable RT?	No
No	Landing Length (in)	36.0	Yes	DWS Provided?	Yes
Yes	Landing Width (in)	48.0	Yes	DWS Contrast?	Yes
Yes	Landing Slope (%)	0.0	Yes	DWS Length (in)	24.0
Yes	Landing X Slope (%)	0.3	No	DWS Full Width?	No
N/A	Landing Curb? (Y/N)	N/A	Yes	DWS Offset LT (in)	2.0
N/A	Shared Landing?	Yes	Yes	DWS Offset RT (in)	5.0
Yes	Gutter Ponding?	No	Yes	Gutter Slope (%)	2.4
Yes	Gutter Lip Ht (in)	0.0	Yes	Gutter X Slope (%)	0.8
N/A	Painted X Walk1?	Yes		Road Slope (%)	1.0
	X Walk 1 Direction	To S		Road X Slope (%)	0.8
	X Walk 1 Width (in)	103.5		Clear Space?	Yes
	X Walk 1 Slope (%)	1.0	N/A	Clear Space to XWalk (in)	N/A
	X Walk 1 X Slope (%)	0.8	Yes	Storm Grate/Utility Hazard?	No
Yes	Ramp inside XWalk1?	Yes		Storm Grate/Utility Type	
Yes	Any Obstructions?	No			N/A
	Obstruction Type		Yes	Surface Condition? (G/P)	Good
			N/A	Curb Slope (%)	0.5

