

Access Compliance Report Public Rights-of-Way (Transit Stops)

Intersection ID: 10023039	Main Street: CENTRE_ST	Cross Street: N/A	Location: W
ADA ID: 455DB7727319	Overall Compliance: No	Severity Score: 50	

Codes/Mitigation Info/Possible Solution	Field Measurements/Component Compliance
---	---



Possible Solutions:

**Remove & Replace Boarding Area.
Remove & Replace Sidewalk To
Boarding Area. Provide Clear Floor
Space.**

Surveyor Notes:

N/A

PROW/ADA:

**402.2, 810.2.3, 810.2.4, 810.3, R302,
R302.6, R308.1.1.2, R404.1**

Compliance	Description	Data
Yes	Boarding Area	Yes
Yes	Boarding Area Width (in)	60.0
Yes	Boarding Area Length (in)	113.0
No	Boarding Area Slope %	5.1
Yes	Boarding Area XSlope %	0.2
Yes	PAR 1 Exist?	Yes
Yes	PAR 1 Width (in)	59.0
Yes	PAR 1 Slope %	0.6
Yes	PAR 1 XSlope %	0.2
N/A	PAR 1 XSlope Location	Perp
No	PAR 2 Exist?	Yes
Yes	PAR 2 Width (in)	59.0
Yes	PAR 2 Slope %	1.9
No	PAR 2 XSlope %	2.8
N/A	PAR 2 XSlope Location	Perp
Yes	Boarding Area Connected to PAR?	Yes
N/A	Road Slope %	0.6
N/A	Shelter	No
No	Clear Floor Space	No
N/A	Clear Floor Space Shelter	No
N/A	Clear Floor Space Width (in)	N/A
N/A	Clear Floor Space Length (in)	N/A
N/A	Clear Floor Space Slope %	N/A
N/A	Clear Floor Space XSlope %	N/A
N/A	Alcove Condition?	No
Yes	Transit Sign?	Yes
Yes	Transit Sign Height (in)	93.0
N/A	Bench?	Yes
Yes	Protruding Objects?	No

CATS Stop ID: 05650

CATS Stop Description: Centre St & Tennessee Ave

CATS Route ID: 3

CATS Route Name: The Plaza

Total Cost: \$ 1900.00

