

# Access Compliance Report Public Rights-of-Way (Transit Stops)

|                           |                        |                    |             |
|---------------------------|------------------------|--------------------|-------------|
| Intersection ID: 10013227 | Main Street: THE_PLAZA | Cross Street: N/A  | Location: N |
| ADA ID: D8FBEA41D874      | Overall Compliance: No | Severity Score: 30 |             |

| Codes/Mitigation Info/Possible Solution | Field Measurements/Component Compliance |
|-----------------------------------------|-----------------------------------------|
|-----------------------------------------|-----------------------------------------|



Possible Solutions:

**Remove & Replace Boarding Area.  
Remove & Replace Sidewalk To  
Boarding Area. Remove & Replace  
Clear Floor Space. Remove or  
Relocate Protruding  
Objects/Obstructions.**

Surveyor Notes:

**N/A**

PROW/ADA:

**305.2, 305.3, 402.2, 810.2.2, 810.2.3,  
810.2.4, 810.3, R302, R302.5, R302.6,  
R308.1.1.1, R308.1.1.2, R404.1,  
R404.2, R404.3**

CATS Stop ID: 31810

CATS Stop Description: **The Plaza & Fairmarket PI**

CATS Route ID: 23

CATS Route Name: **Shamrock Drive**

Total Cost: \$ 4650.00

| Compliance | Description                     | Data |
|------------|---------------------------------|------|
| Yes        | Boarding Area                   | Yes  |
| Yes        | Boarding Area Width (in)        | 60.0 |
| No         | Boarding Area Length (in)       | 54.0 |
| No         | Boarding Area Slope %           | 4.7  |
| Yes        | Boarding Area XSlope %          | 1.2  |
| No         | PAR 1 Exist?                    | Yes  |
| Yes        | PAR 1 Width (in)                | 48.0 |
| Yes        | PAR 1 Slope %                   | 1.2  |
| No         | PAR 1 XSlope %                  | 4.7  |
| N/A        | PAR 1 XSlope Location           | Perp |
| No         | PAR 2 Exist?                    | Yes  |
| Yes        | PAR 2 Width (in)                | 48.0 |
| Yes        | PAR 2 Slope %                   | 1.3  |
| No         | PAR 2 XSlope %                  | 4.6  |
| N/A        | PAR 2 XSlope Location           | Perp |
| Yes        | Boarding Area Connected to PAR? | Yes  |
| N/A        | Road Slope %                    | 0.7  |
| N/A        | Shelter                         | No   |
| No         | Clear Floor Space               | Yes  |
| N/A        | Clear Floor Space Shelter       | No   |
| No         | Clear Floor Space Width (in)    | 24.0 |
| No         | Clear Floor Space Length (in)   | 36.0 |
| No         | Clear Floor Space Slope %       | 8.4  |
| Yes        | Clear Floor Space XSlope %      | 0.7  |
| N/A        | Alcove Condition?               | Yes  |
| Yes        | Transit Sign?                   | Yes  |
| Yes        | Transit Sign Height (in)        | 93.0 |
| N/A        | Bench?                          | Yes  |
| No         | Protruding Objects?             | Yes  |

