## Development Standards Rezoning Petition No. 2003-13

## I. GENERAL COMMITMENT:

A. Development of the real estate identified on this Technical Data Sheet, consisting of 6.89 acres, more or less (the "Site"), will be governed by the etandarda established under the zoning ordinance of the City of Charlotte (the "Ordinance") for the R-8MF zoning district unless more stringent standards are established by these Development Standards or this Technical Data Sheet.

B. The configurations, placements, and sizes of the residential buildings, parking areas, driveways, roads and common open spaces shown on the Schematic Site Plan which accompanies this Technical Data Sheet are echematic and conceptual in nature and may be altered and/or modified based upon final design, development and construction documents and site and topographical construction within the maximum building limit lines established on this Technical Data Sheet.

II. PERMITTED USES:

The Site may be developed with up to 53 for eale, single family attached dwelling units, together with any incidental or accessory uses associated therewith which are permitted under the Ordinance by right or under prescribed conditions in the R-8MF Zoning District.

III. VEHICULAR ACCESS POINTS:

A. The number of access points to and from the Site shall be limited to those shown on the Technical Data Sheet.

B. Access points shall be located in the general areas depicted on this Technical Data Sheet. The final location of each access point is subject to any modifications required to accommodate final site and construction plans/design, and site/topographic constraints, and to any adjustments required for approval by the Charlotte Department of Transportation and/or the North Carolina Department of Transportation.

C. The Petitioner shall provide for a "stub" street connection at the end of the driveway located in the southwest corner of the Site in order to permit vehicular connection to the abutting property to the west, provided that any such connection shall be made only in the event such abutting property is developed and used for residential purposes.

M. DESIGN GUIDELINES:

A. ARCHITECTURAL TREATMENT

(1) The primary exterior building materials to be employed in the construction of the single family attached dwelling units shall be brick and cement fiber board (i.e. Hardi-Plank). A minimum of 20% of the frontelevation of each dwelling unit will consist of brick materials.

(2) The maximum height of any buildings constructed on the Site shall not exceed 40 feet.

(3) The single family attached dwelling units may be constructed with or without garages in the discretion of the

B. YARD RESTRICTIONS AND BUFFER REQUIREMENTS

(1) In every instance the elde yard, setback, and rear yard requirements imposed under the Ordinance will be eatisfied with respect to the development taking place within the Site, unless more stringent requirements are established under these Development Standards.

(2) Buffer areas shall be maintained along portions of the Sits boundary in the manner shown on this Technical Data Sheet and in accordance with the standards of the Ordinance. In the event that an adjacent parcel is either rezoned to a zoning district or devoted to a use that eliminates or reduces the buffer requirements on the Site, then the Petitioner may reduce or eliminate, as the case may be, the buffers set out on the Technical Data Sheet accordingly.

C. OFF STREET PARKING

Off street parking shall meet the minimum standards established under the Ordinance.

D. STORM WATER MANAGEMENT

(1) Storm water runoff from the Site will be managed through proven techniques which eatlefy the etandards imposed by the City of Charlotte. During the permitting stage of development, the Petitioner shall have the receiving drainage eyetem, located directly downstream from the Site at the next receiving channel abutting the Site of the south, analyzed to ensure that it will not be taken out of standard due to the development contemplated by this rezoning petition. If it is found that this development will cause such receiving storm drainage system to be taken out of standard, the Petitioner shall provide adequate detention on the Site or will otherwise take such reasonable steps as may be needed to prevent this from occurring. Should the existing receiving drainage system be deemed to be out of standard prior to development of this Site, the Petitioner shall only be responsible for providing adequate detention, reasonable under the circumstances, to ensure that such system will not be additionally overburdened; it is expressly understood that Petitioner shall not be responsible for correcting existing conditions that cause the exeting, receiving drainage system to be out of standard prior to the development of the Site.

(2) Surface level storm water detention shall not be located within the buffers.

E. SIDEWALKS

(1) A 5 foot wide eldewalk and an 8 foot wide planting etrip vill be inetalled along Providence Road West.

(2) Petitioner will provide internal eldewalks 5 feet in width subtantially the manner as depicted on the Schematic Site
Plan attached hereto.

F. OPEN SPACE

Development of the Site shall include common open space area in the general locations shown on the Schematic Site Plan. The specific locations and dimensions of such common cen space areas may be altered and/or modified based upon final design, development and construction documents an site and topographical constraints.

G. LANDSCAPING, SCREENING AND TREE PRESERVATION

(1) Landscaping and screening shall, at a minimum, satisfy the requirements of Section 12.303 of the Ordinance.

(2) Landecaping will be inetalled in stages in accordance with ne Ordinance as the Site is developed.

(3) The landscape/screening treatment along Providence Road lest will include (2) large maturing trees, 8' minimum height, per 100'; (1) email maturing or flowering tree, 6' minimum height, per 100' and (20) shrube, 24" minimum height per 100'.

(4) It is contemplated that garbage disposal shall be handled if way of roll out cans and pick up by a private service. If dumpeters or trash receptacle "corrals" are installed on the Sis, they will be screened with solid enclosures with gates. Pursuant to Section 12.403 of the Ordinance, if public trash cliection is provided to the Site, any required dumpeters, trash receptacles and recycling facilities will be located in the reas generally depicted on the Schematic Site Plan, provided, however, other improvements, such as parking and ladecaping areas may be located in such areas if the private roll-out trash collection is used.

(5) Tree protection and planting within the Site will eatlefy the provisions of the City of Charlotte Tree Ordinance. Without limiting the foregoing, those mature trees located within the bifer area along the westerly boundary of the Site and in certain portions of the common open space to be located on 18 Site, each as specifically designated on the Technical Data Sheet, will be preserved.

H. SIGNS

(1) All eigns placed on the Site will be erected in accordance ith the requirements of the Ordinance.

(2) A master eignage and graphice eyetem will be adopted andimplemented throughout the Site.

I. LIGHTING

(1) All freestanding lighting fixtures installed will be uniform in saign and the maximum height of any such lighting fixture, including its base, may not exceed 15 feet in height.

ture, including its base, may not exceed 15 feet in height.

(2) All direct lighting within the site (except streetlights which may be erected along Providence Road West or any Internal private etreete) will be capped to project light downward and olerwise designed such that direct illumination does not extend past any adjacent property line. Consideration will be gen to the impact of lighting both within and without the perimeter of the Site. Items for consideration will include interity, outoff angles, color, energy efficiency, and shielding sources of light, the intent being to eliminate glare towards pulc streets and adjacent properties.

FIRE PROTECTION

Fire protection will be provided in accordance with the City of harlotte's standards.

entrance to the Site within Providence Road West in accordancewith applicable CDOT standards.

APPROVED BY CITY COUNCIL

ATE 3/17/03

The Petitioner agrees to dedicate and convey (by quitolaim del and subject to reversionary interest in any property not used for right-of-way purposes in the future) such portions ofthe Site as may be needed to provide for 50 feet of right-of-way south of the existing centerline of Providence Ros West prior the issuance of any building permits for improvements to the Site. In addition, the Petitioner agrees to rovide for the construction of a left turn lane into the

VI, AMENDMENTS TO THE REZONING PLAN:

The owner or ownere of the Site, in accordance with the Ordance, may apply for future amendments to this Technical Data Sheet and these Development Standards.

VII. BINDING EFFECT OF THE REZONING PETITION:

V. RIGHT OF WAY DEDICATION AND IMPROVEMENTS

If the Petitioner's rezoning petition is approved, the developmet program established under these Development Standards and this Technical Data Sheet shall, unless amended in the maner provided under the Ordinance, be binding upon and inure to the benefit of the Petitioner and the owners (from tim to time) and their respective heirs, devisees, personal representatives, successors in interest and assigns.

Throughout these Development Standards, the terms, "Petitions and "Owner" shall be deemed to include the heirs, devisees, personal representatives, successors in interest and adjans of the Petitioner or the owner or owners of the Site from time to time who may be involved in any future development thereof.

SOLUTIONS

andscape Architecture
Park Planning
Civil Engineering

5311 Seventy-Seven Center Drive Suite 82 • Charlotte, NC 28217 704.521.9880 • Fax 704.521.8955 E-Mail info@sitesolutionspa.com

eals:

Iry Court Townhomes k, USA / Llewellyn Development, LL

Project No: 2433

Drawn By: P. Gorsuch

Designed By: P. Hobbs

Checked By: P. Hobbs

11/21/02

Revisions:

Revision 1 1/21/03

Revision 2 2/13/03

Revision 3 3/10/03


Revision 4 4/23/03

(INSERT "CENTERLINE" IN V.)

Sheet Title

Rezoning Technical Data

heet No: RZ-1



## Development Data

TAX PARCEL NUMBER:

223-132-04 223-132-05

R-3 EXISTING ZONING:

R-8MF (CD) PROPOSED ZONING: 6,89 AC GROSS AREA: 6.72 AC

MAX. UNITS ALLOWED: 53 PROPOSED UNITS: 8 DU/AC MAX. DENSITY ALLOWED:

7.89 DU/AC PROPOSED DENSITY: 80 SPACES REQUIRED PARKING: 94 SPACES

> 8 SPACES IN GARAGES 102 TOTAL SPACES

REQUIRED OPEN SPACE: 50%

PROPOSED OPEN SPACE: 4.17 AC (60.5%)

EXISTING TREELINE

PROPOSED TREELINE AFTER CLEARING

EXISTING TREE TO REMAIN


PROPOSED LARGE MATURING DECIDUOUS TREE

PROPOSED SHRUBS

The building configurations, placements and sizes, as well as the locations of streets and parking area are schematic in nature and may be altered or modified during design development and construction

## FOR PUBLIC HEARING

**PETITION NO. 2003-13** 



APPROVED BY CITY COUNCIL

Civil Engineering 5311 Seventy—Seven Center Drive Suite 82 • Charlotte, NC 28217 Ph. 704.521.9880 • Fax 704.521.8955 E—Mail info⊕sitesolutionspa.com

ownhome

oventry

Project No: P. Gorsuch Drawn By: P. Hobbs P. Hobbs 11/21/02

1/21/03 2/13/03 Revision Revision 2

Sheet Title:

Schematic Site Plan