

TAX PARCEL NUMBER:	031-411-18
SITE ACREAGE:	13.368 AC
CURRENT ZONING:	R-4 LW-PA
PROPOSED ZONING:	MX-1 LW-PA INNOVATIVE
PROPOSED DENSITY:	3.38 DU/AC
DEVELOPMENT TYPE:	(LOW DENSITY OPTION) (24% IMPERVIOUS AREA) RESIDENTIAL (DETACHED)
PROPOSED USE:	53
TOTAL UNITS:	53
TYPICAL LOT WIDTHS:	30', 35' & 40'
SIDE YARD:	3'
FRONT SETBACK:	10'
REAR YARD:	10'
CORNER LOT SIDE YARD:	5'
MIN. REQUIRED OPEN SPACE:	10%
PROVIDED OPEN SPACE:	51.9% (6.89 AC)
OPEN SPACE EXCLUDING PONDS:	3.83 AC
OPEN SPACE IN PONDS:	3.06 AC
PERIMETER (LOTS 15-20):	
PERIMETER LOTS REAR SETBACK:	20'

DEVELOPMENT SUMMARY				
CURVE	RADIUS	ARC LENGTH	CHORD LENGTH	CHORD BEARING
C1	225.00'	212.98'	205.12'	N 82°38'42" E
C2	485.00'	148.80'	148.02'	S 79°00'52" E



Mc² ENGINEERING, INC.
8624 LAUREL RUN DRIVE
CHARLOTTE, NC 28269
PHONE 704.363.7375





WALDEN PONDS SUBDIVISION
DEVELOPED BY:
RR MANAGEMENT COMPANY, LLC
1220 SOUTH KING DRIVE
CHARLOTTE, NC 28207
P: 704.372.4821
F: 704.372.5631

SCHEMATIC SITE PLAN

REVISIONS	
1	12/16/04 STAFF COMMENTS
2	2/16/05 STAFF COMMENTS
3	2/18/05 STAFF COMMENTS

APPROVED BY CITY COUNCIL
DATE: 2-18-05

CAD FILE: 2004-002 REZN.DWG
PROJECT NO.: 2004-002
DESIGNED BY: JOM
DATE: SEPTEMBER 27, 2004





THE DEVELOPMENT DEPICTED ON THIS REZONING SCHEMATIC SITE PLAN IS MERELY SCHEMATIC IN NATURE AND INTENDED ONLY TO ILLUSTRATE THE POSSIBLE ARRANGEMENT OF USES AND DEVELOPMENT ON THE SITE. THE EXACT DETAILS OF THE CONFIGURATION, PLACEMENT AND SIZE OF THE INDIVIDUAL SITE ELEMENTS, INCLUDING THE BUILDINGS, SHALL BE ESTABLISHED DURING THE DESIGN PHASE AND SHALL BE GOVERNED BY THE REQUIREMENTS OF THE ZONING ORDINANCE, APPLICABLE CODE REQUIREMENTS AND THE DEVELOPMENT CRITERIA CALLED OUT ON THE TECHNICAL DATA SHEET OF THESE REZONING PLANS, AND MAY BE ALTERED OR MODIFIED DURING DESIGN DEVELOPMENT WITHIN THE MAXIMUM BUILDING ENVELOPE LINES ESTABLISHED ON THE TECHNICAL DATA SHEET. IT IS UNDERSTOOD THAT MODIFICATIONS ARE ALLOWED PER SECTION 6.206(C) OF THE ZONING ORDINANCE.

OVERVIEW


RZ2.0

FOR PUBLIC HEARING
REZONING PETITION #2005-06



TAX PARCEL NUMBER:	031-411-18
SITE ACREAGE:	13.368 AC
CURRENT ZONING:	R-4 LW-PA
PROPOSED ZONING:	MX-1 LW-PA INNOVATIVE
PROPOSED DENSITY:	3.38 DU/AC
DEVELOPMENT TYPE:	(LOW DENSITY OPTION) (24% IMPERVIOUS AREA) RESIDENTIAL (DETACHED)
PROPOSED USE:	53
TOTAL UNITS:	53
TYPICAL LOT WIDTHS:	30', 35' & 40'
SIDE YARD:	3'
FRONT SETBACK:	10'
REAR YARD:	10'
CORNER LOT SIDE YARD:	5'
MIN. REQUIRED OPEN SPACE:	10%
PROVIDED OPEN SPACE:	51.9% (6.89 AC)
OPEN SPACE EXCLUDING PONDS:	3.83 AC
OPEN SPACE IN PONDS:	3.06 AC
PERIMETER (LOTS 15-20):	
PERIMETER LOTS REAR SETBACK:	20'

DEVELOPMENT SUMMARY				
CURVE	RADIUS	ARC LENGTH	CHORD LENGTH	CHORD BEARING
C1	225.00'	212.98'	205.12'	N 82°38'42" E
C2	485.00'	148.80'	148.02'	S 79°00'52" E



Mc² ENGINEERING, INC.
8624 LAUREL RUN DRIVE
CHARLOTTE, NC 28269
PHONE 704.363.7375

WALDEN PONDS SUBDIVISION
DEVELOPED BY:
RR MANAGEMENT COMPANY, LLC
1220 SOUTH KING DRIVE
CHARLOTTE, NC 28207
P: 704.372.4821
F: 704.372.5631

TECHNICAL DATA SHEET

REVISIONS	
1	12/16/04 STAFF COMMENTS
2	2/16/05 STAFF COMMENTS
3	2/18/05 STAFF COMMENTS

APPROVED BY CITY COUNCIL
DATE: 2-18-05

CAD FILE: 2004-002 REZN.DWG
PROJECT NO.: 2004-002
DESIGNED BY: JOM
DATE: SEPTEMBER 27, 2004

RZ2.1

FOR PUBLIC HEARING
REZONING PETITION #2005-06

- DEVELOPMENT STANDARDS**
- Development of the site will be controlled by the standards depicted on this site plan and by the standards of the Charlotte Zoning Ordinance. The development depicted on this plan is intended to reflect the arrangement of proposed uses on the site, but the exact configuration, placement, and size of individual site elements may be altered or modified within the limits prescribed by the ordinance during the design development and construction phases within the building envelope line as shown on the plan per Section 6.2 of the Zoning Ordinance.
 - The use of the site will be for the construction of single-family detached homes on individual lots along with related accessory uses under the MX-1 district standards. None of the property covered by the restrictions of this petition may be used for any non-residential use. The Petitioner will limit development of the site to comply with the 24% impervious cover requirements of the Lake Wylie watershed standards. The site will be designed to utilize one or more of the existing small ponds as part of the water management for the site to the extent practical.
 - Any detached lighting on the site will be limited to 20 feet in height unless City standards require streetlights to be higher. The Petitioner will install pedestrian scale lighting as part of the site improvements.
 - Signage will be permitted in accordance with applicable Zoning standards.

- Parking will be provided which will meet or exceed the standards of the Zoning ordinance.
- Access will be provided by a street connection to Tom Sadler Rd and by future connections to other properties.
- The open space on the site will be devoted primarily to passive recreation and may include a combination of site elements including trails, seating and viewing areas, and small gathering spaces or structures such as a gazebo or shelter. The size of the site and the nature of the site with its extensive open space, lakes, and tree save areas preclude the establishment of a significant active open space component.
- The Petitioner reserves the right to install a decorative fence or combination of a decorative fence and landscaping along the east side of the site as generally depicted on the technical data sheet as part of the overall site development and landscaping. In addition, the Petitioner will install a fence or wall along the rear lot lines of the 5 lots along the western side of the site as generally depicted on the technical data sheet to provide a physical and visual separation between these lots and the existing single family home on the adjoining tract. The Petitioner may supplement this fence or wall with additional landscaping as part of the overall site development and landscaping.
- The Petitioner, in accordance with the provisions of Section 11.208, "Innovative Development Standards", may propose modifications to the following standards:

- Street right-of-way widths.
 - Street type, dimensions, and construction standards.
 - Minimum lot size.
 - Setbacks, side, and rear yards.
 - Lot width, and
 - Open space elements, but not minimum amount of open space.
- In conjunction with community input, the Petitioner will establish the following building and design guidelines for the homes to be built on the site. These details will be added to the covenants and restrictions that will govern the development and use of the site.
 - The minimum floor area for any home constructed on the site will be 1,600 sq. ft.
 - All of the homes will have 9' ceilings on the first floor.
 - All of the homes will have at least one enclosed garage.
 - In addition to normally expected rooms such as kitchens, bathrooms, formal rooms, or family rooms, the homes will have three rooms that could be used as bedrooms or for other purposes, such as a den, study, or home office.
 - All homes will be wired for phone and cable service. Optional wiring for security, audio, video, or other systems may also be included. Fireplaces will also be an option in all homes.
 - The homes will have a 9/12 residential roof pitch on the main portion of the structure (excluding design elements such as porches, dormers, etc.) and may use a variety of roofing materials.
 - No garage entrance will be located within 20' of the outside edge of the sidewalk.

- The exterior siding of all homes exclusive of doors, windows and window frames, dormers, and gables, will be composed of a combination of building materials including brick, stone, or other similar durable masonry product, wood, or other durable product, and will exclude the use of vinyl siding.
- The development will be furnished with uniform mailboxes.
- No commercial vehicle parking will be permitted.
- A home owners association will be established for the entire community to enforce these and other covenants and restrictions.
- Any homes that may be constructed on a slab foundation will be constructed so that the portion of the foundation that faces the street will have the appearance of a raised foundation through the use of brick, stone, or other similar products, which will also be used for foundation treatment elsewhere in the development.
- The Petitioner acknowledges that other standard development requirements imposed by other city ordinances, such as those that regulate streets, sidewalks, trees, and site development, may apply to the development of this site. These requirements are not zoning regulations, are not administered by the Zoning Administrator, and are not separate zoning conditions imposed by this site plan.
- Throughout this Rezoning Petition, the terms "Owner", "Owners", "Petitioner" or "Petitioners", shall, with respect to the Site, be deemed to include the heirs, devisees, personal representatives, successors in interest and assignees of the owner or owners of the Site who may be involved in its development from time to time.

