

Petition No. 2014-037
 Petitioner: Charlotte-Mecklenburg Planning Department

JUN 16 2014

**AN ORDINANCE AMENDING APPENDIX A
 OF THE CITY CODE –ZONING ORDINANCE**

ORDINANCE NO.

BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF CHARLOTTE:

Section 1. Appendix A, "Zoning" of the Code of the City of Charlotte is hereby amended as follows:

A. CHAPTER 12: DEVELOPMENT STANDARDS OF GENERAL APPLICABILITY

1. PART 5: SPECIAL REQUIREMENT FOR CERTAIN USES

- a. Amend Table 12.540-1, "Outdoor Recreation Screening and Buffering Requirements" by clarifying the buffer and/or separation distance requirements in the table and specifying how the separation distance is measured in a new footnote #4. In addition, add a reference to Section 12.303. The revised table shall read as follows:

Table 12.540-1 Outdoor Recreation Screening and Buffering Requirements


	OUTDOOR RECREATIONAL USES THAT ARE PART OF A PLANNED DEVELOPMENT		OUTDOOR RECREATIONAL USES THAT ARE NOT PART OF A PLANNED DEVELOPMENT
	Where Abutting A Lot In The Same Planned Development	Where Abutting A Residentially Zoned Or Used Lot That Is Not Part Of A Planned Development	Where Abutting A Lot That Is Residentially Zoned Or Used
	Buffer and/or separation distance ⁴ from lots in the same planned development	Buffer and/or separation distance ⁴ from lots outside the planned development that are residentially zoned or used	Buffer and/or separation distance ⁴ from residentially zoned or used properties
Recreational Facilities ¹	20' separation	100' separation and a Class C Buffer (see 12.302)	100' separation and a Class C Buffer (see 12.302)
Parking Areas	5' Parking Lot Screen (see 12.211 and 12.303)	Class C Buffer (see 12.302)	Class C Buffer (see 12.302)
Service Areas and Facilities ²	Class C Buffer (see 12.302)	100' separation and a Class C Buffer (see 12.302)	100' separation and a Class C Buffer (see 12.302)
Golf Courses ³	20' separation	Class C Buffer (see 12.302)	Class C Buffer (see 12.302)

¹ Recreational facilities include pools, tennis courts, baseball fields, soccer fields, picnic shelters, clubhouses, pro shops, exercise or fitness centers, snack bars, as well as other principal and accessory uses intended primarily for the use of patrons.

- ² Services Areas include maintenance facilities, storage buildings and structures, dumpsters, loading areas and other accessory uses intended primarily for the servicing of the recreational facility or equipment used therein.
- ³ Golf courses include driving ranges, practice and putting greens, and tee boxes. Buildings associated with a golf course shall meet the requirements for Recreational facilities or service areas depending on their intended use.
- ⁴ Measured from the closest edge of any recreational facility, service area, service facility or golf course to lot lines.

Section 2. That this ordinance shall become effective upon its adoption.

Approved as to form:


City Attorney

I, _____, City Clerk of the City of Charlotte, North Carolina, DO
HEREBY CERTIFY that the foregoing is a true and exact copy of an Ordinance adopted
by the City Council of the City of Charlotte, North Carolina, in regular session convened
on the 16th day of June, 2014, the reference having been made in Minute Book ____, and
recorded in full in Ordinance Book _____, Page(s) _____.

WITNESS my hand and the corporate seal of the City of Charlotte, North Carolina, this
____ day of _____, 2014.